BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT16703

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/09/2014-15, Date: 23.01.2015

Improvements to roads near Sai Baba temple in ward no. 08

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M.B. Hombal	
				In Figures	In Words
1	66.94	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications. - RCC grade M20 and above	Cum	945.00	Rupees Nine Hundred Forty Five Only
2	106.92	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	72.00	Rupees Seventy Two Only
3	200.82	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per	Cum	4700.00	Rupees Four Thousand Seven Hundred Only
4	133.88	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete	Cum	5650.00	Rupees Five Thousand Six Hundred Fifty Only
5	1338.80	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead	sqm	96.00	Rupees Ninety Six Only
6	30.40	Providing groove cutting for cement pavement wifth of 5mm to 10mm and depth 800mm-100mm including cost of cutting machine, generator and HOM of machinery, including cost of blade, coolant etc, including cleaning of groove and providing sand and hot bitumen fillarsm and filler metal etc including of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications	sqm	118.00	Rupees One Hundred Eighteen Only
7	173.86	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	71.00	Rupees Seventy One Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92